

# Geotechnical Data Report

Calais BHF 037-2 (10)

Vermont Route 14, Bridge 74 Over Pekin Brook

Calais, Vermont

PIN: 11a218

May 01, 2014

Terracon Project No. J1145111

**Prepared for:**

Vermont Agency of Transportation  
Montpelier, Vermont

**Prepared by:**

Terracon Consultants, Inc.  
Manchester, New Hampshire

[terracon.com](http://terracon.com)

**Terracon**

Environmental



Facilities



Geotechnical



Materials

May 01, 2014



Vermont Agency of Transportation  
Materials and Research  
One National Life Drive  
Montpelier, Vermont 05633

Attn: Mr. Christopher Benda, PE  
P: [802] 828-6910  
E: chris.benda@state.vt.us

Re: Geotechnical Data Report  
Calais BHF 037-2 (10)  
Vermont Route 14, Bridge 74 Over Pekin Brook  
Calais, Vermont  
PIN: 11a218  
May 1, 2014  
Terracon Project No. J1145111


Dear Mr. Benda:


Terracon Consultants, Inc. (Terracon) has completed the geotechnical engineering services for the above referenced project. This study was performed in general accordance with our proposal number PJ1140027 dated February 13, 2014. This report presents the findings of the subsurface exploration and laboratory testing for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have questions concerning this report, or if we may be of further service, please contact us.

Sincerely,  
**Terracon Consultants, Inc.**

  
Anant Panwalkar  
Senior Project Engineer, P.E.

  
Lawrence J. Dwyer, P.E.  
Principal

A circular professional engineer seal for the State of Vermont. The outer ring contains the text "STATE OF VERMONT" at the top and "PROFESSIONAL ENGINEER" at the bottom, separated by two stars. The inner circle contains the name "JAMES DWYER" at the top, the license number "NO. 018-0008265" in the center, and the word "LICENSED" at the bottom.

Enclosures  
cc: 1 – Client (PDF)  
1 – File

Terracon Consultants, Inc. 77 Sundial Ave. Suite 401W Manchester, New Hampshire 03103  
P [603] 647 9700 F [603] 647 4432 [terracon.com](http://terracon.com)

Environmental

Facilities

Geotechnical

Materials

	Page
<b>1.0 INTRODUCTION .....</b>	<b>1</b>
<b>2.0 PROJECT INFORMATION .....</b>	<b>1</b>
2.1 Project Description .....	1
2.2 Site Location and Description .....	2
<b>3.0 SUBSURFACE CONDITIONS .....</b>	<b>2</b>
3.1 Geology .....	2
3.2 Typical Profile .....	2
3.3 Groundwater .....	3
3.4 Laboratory Testing .....	3
<b>4.0 GENERAL COMMENTS .....</b>	<b>3</b>

#### **APPENDIX A – FIELD EXPLORATION**

Exhibit A-1	Site Location Map
Exhibit A-2	Exploration Location Plan and Geologic Cross Section
Exhibit A-3	Field Exploration Description
Exhibit A-4 to A-9	Boring Logs

#### **APPENDIX B – LABORATORY TESTING**

Exhibit B-1	Laboratory Testing Results
-------------	----------------------------

**GEOTECHNICAL DATA REPORT**  
**Calais BHF 037-2 (10)**  
**Vermont Route 14, Bridge 74 Over Pekin Brook**  
**CALAIS, VERMONT**  
**PIN:11a218**  
**Terracon Project No. J1145111**  
**May 1, 2014**

## **1.0 INTRODUCTION**

This geotechnical data report presents the results of our geotechnical exploration performed for the proposed replacement of Bridge No. 74 carrying Vermont Route 14 over Pekin Brook in Calais, Vermont.

Our geotechnical engineering scope of services included advancing two test borings, designated B-1 and B-2, as identified on the Geotechnical Services Request Form prepared by Vermont Agency of Transportation (VAOT). The scope included two borings drilled to a maximum of 100 feet with rock cores taken if refusal was encountered within 50 feet. Terracon finalized the boring depths and sampling intervals in general accordance with the VAOT guidelines "MREI 11-01 Geotechnical Guidelines for the Subsurface Investigation Process" and our discussions with VAOT staff. Subsequently, the scope was modified during drilling program to extend the borings and to obtain confirmatory bedrock cores. B-1 was terminated in weathered bedrock at 109 feet. B-2 was re-drilled 5 feet south of original location to obtain a confirmatory bedrock core and terminated in bedrock at 126 feet depth.

Site Location Map is included on Exhibit A-1 in Appendix A. The boring locations are shown on Exhibit A-2: Exploration Location Plan and Geologic Cross Section in Appendix A.

## **2.0 PROJECT INFORMATION**

### **2.1 Project Description**

<b>Item</b>	<b>Description</b>
<b>Site layout</b>	See Appendix A, Exhibit A-2: Exploration Location Plan and Geologic Cross Section.
<b>Structure</b>	The project consists of replacing existing 34.8 feet long and 44 feet wide concrete T-beam Bridge 74 carrying Vermont 14 over Pekin Brook in Calais, Vermont.
<b>Cut and fill slopes</b>	Minimum cut and fill slopes are anticipated.

Item	Description
<b>Finish Elevation</b>	Anticipated to be similar grade as the existing bridge and roadways.

## 2.2 Site Location and Description

Item	Description
<b>Location</b>	The subject bridge is located approximately 100 feet south of the intersection of Vermont Route 14 and Pekin Brook Road in Calais, Vermont.
<b>Existing improvements</b>	Existing concrete t-beam bridge constructed circa 1928 and re-constructed in 1981.
<b>Current ground cover</b>	Paved roadway.
<b>Existing topography</b>	Roadway elevation (EI) approximately EI 717 feet. Streambed approximately EI 708 feet. Negligible grade difference from one side of the bridge to the other.

## 3.0 SUBSURFACE CONDITIONS

### 3.1 Geology

A preliminary report prepared by AOT provided a summary of available geological information. Based on the information provided in the preliminary report and the Surficial Geology Map of Vermont, the subsurface soils consist of deep deposits of alluvial sands overlying silt-clay and clay. Bedrock Geology Map of Vermont 2011 indicates bedrock is part of the Waits River Formation and likely consists of carbonaceous phyllite and limestone.

### 3.2 Typical Profile

Based on the results of the borings, subsurface conditions can be generalized as follows:

Stratum	Approximate Depth to Bottom of Stratum (feet)	Material Description	Consistency/ Density
<b>Bituminous Pavement</b>	0.5	N/A	N/A
<b>Fill</b>	4.0 to 6.0	Fine to coarse sand, little silt. Brown, dry.	Loose to very dense.
<b>Sand with Silt</b>	14.0 to 16.0	Well sorted sand, little silt, gray, wet.	Very loose to medium dense.

## Geotechnical Data Report

Calais BHF 037-2 (10) Bridge No.74 ■ Calais, VT

May 1, 2014 ■ Terracon Project No. J1145111



Stratum	Approximate Depth to Bottom of Stratum (feet)	Material Description	Consistency/ Density
Silt	105.0 to 115.0	Silt, trace sand, trace clay at deeper depths, gray, wet.	Very soft to stiff.
Sand and Silt	121.0	Fine grained sand and silt, gray, wet.	Dense
Weathered Bedrock	121.5 (B-2)	Gray, highly weathered rock, wet.	N/A.
Bedrock	N/A	Gray, whitish muscovite-biotite-quartz phyllite, tight joints dipping from 0 to 55 degrees.	moderately hard to hard

Interpreted subsurface profile along the bridge centerline is presented on Exhibit A-2 in Appendix A. Conditions encountered at each boring location are indicated on the individual boring logs. Stratification boundaries on the exploration logs represent the approximate location of changes in soil types; in situ, the transition between materials may be gradual. Details for each of the explorations can also be found on the logs in Appendix A of this report.

### 3.3 Groundwater

Explorations were observed during drilling for the presence of groundwater. Observed groundwater depths varied from 16.0 feet at B-1 to 9.0 feet at B-2 (El 705 feet to El 711 feet) at the time of drilling. Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff, brook elevation, and other factors not evident at the time the explorations were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than the levels indicated on the boring logs. Groundwater level fluctuations should be considered when developing the design and construction plans for the project.

### 3.4 Laboratory Testing

Laboratory testing was performed on soil samples obtained from the test borings to assist in classification and evaluate engineering properties. Laboratory testing was performed by VAOT staff in the VAOT facility located in Berlin, Vermont. The results of the laboratory tests are presented in Appendix B of this report.

## 4.0 GENERAL COMMENTS

The interpretations presented in this report are based upon the data obtained from the borings performed at the indicated locations and from other information discussed in this report. This report does not reflect variations that may occur between borings, across the site, or due to the

**Geotechnical Data Report**

Calais BHF 037-2 (10) Bridge No.74 ■ Calais, VT

May 1, 2014 ■ Terracon Project No. J1145111




modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. If variations appear, we should be immediately notified so that further evaluation and supplemental recommendations can be provided.

The scope of services for this project does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.


This report has been prepared for the exclusive use of our client for specific application to the project discussed and has been prepared in accordance with generally accepted geotechnical engineering practices. No warranties, either express or implied, are intended or made. Site safety, excavation support, and dewatering requirements are the responsibility of others. In the event that changes in the nature, design, or location of the project as outlined in this report are planned, the conclusions and recommendations contained in this report shall not be considered valid unless Terracon reviews the changes and either verifies or modifies the conclusions of this report in writing.

**APPENDIX A**  
**FIELD EXPLORATION**






SCALE: 1:24 000



CONTOUR INTERVAL 6 METERS  
NATIONAL GEODETIC VERTICAL DATUM OF 1929



QUADRANGLE LOCATION  
SOURCE:  
USGS PLAINFIELD, VT  
1986

Project Mngr:	ASP	Project No.	J1145111
Drawn By:	MCR	Scale:	AS SHOWN
Checked By:	ASP	File No.	J1145111.dwg
Approved By:	LJD	Date:	April 2014

**Terracon**

77 Sundial Ave. Manchester, NH 03103  
PH. (603) 647-9700 FAX (603) 647-4432


**SITE LOCATION MAP**  
VT Route 14, Bridge 74 Over Pekin Brook  
CALAIS, VERMONT  
BHF 037-2(10)

**EXHIBIT**

**A-1**




N:\PROJECTS\2014\J1145111\Working Files\Diagrams-Drawings-Figures\J1145111.DWG





BORING CHART

BORING	STATION	OFFSET	NORTHING	EASTING
B-1	114.375	26.00LT	1654568.0392	Y=668328.0399
B-2	116.150	19.00RT	1654651.2557	Y=668489.6772



NOTES:

1. EXPLORATION LOCATION PLAN WAS PREPARED FROM A PLAN PROVIDED BY THE VERMONT AGENCY OF TRANSPORTATION.
2. TEST BORINGS SHOWN AS B-1 AND B-2 WERE ADVANCED ON MARCH 10 THROUGH MARCH 19, 2014 UNDER THE DIRECTION OF TERRACON WITH EQUIPMENT OWNED AND OPERATED BY DRILEX OF WEST BOYLSTON, MA. TEST BORING B-2 WAS REDRILLED ON APRIL 9 AND 10, 2014 UNDER THE DIRECTION OF TERRACON WITH EQUIPMENT OWNED AND OPERATED BY CRAWFORD DRILLING.
3. DATA CONCERNING THE VARIOUS STRATA HAVE BEEN INTERPOLATED AT BORING LOCATIONS ONLY. THE STRATIGRAPHY BETWEEN BORINGS MAY VARY FROM THAT SHOWN.
4. THE APPROXIMATE LOCATIONS OF THE TEST BORINGS WERE LOCATED BY MEASURING FROM EXISTING SITE FEATURES. THE LOCATIONS SHOULD BE CONSIDERED ACCURATE TO THE DEGREE IMPLIED BY THE METHOD USED.
5. USE OF THIS PLAN IS LIMITED TO THE ILLUSTRATION OF THE APPROXIMATE LOCATION OF THE TEST BORINGS AND OTHER PERTINENT SITE FEATURES. OTHER USE OF THIS PLAN WITHOUT PERMISSION FROM TERRACON IS PROHIBITED.



STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

Terracon

77 Sundial Ave. Manchester, NH 03103  
PH. (603)647-9700 FAX (603) 647-4432

EXHIBIT A-2

EXPLORATION LOCATION PLAN AND GEOLOGIC CROSS SECTION

Project Name: VT Route 14, Bridge 74 Over Pekin Brook  
Location: Calais, Vermont  
Number: BHF 037-2(10)

### **Field Exploration Description**

Two test borings were completed at the site from March 10, 2014 through April 10, 2014. Terracon personnel monitored the advancement of the soil borings within the project site. Soil borings were advanced using an all-terrain vehicle mounted rotary drill rig, owned and operated by Drillex Environmental of West Boylston, Massachusetts and Crawford Drilling Services of Gardner, MA. B-1 and B-2 were advanced using mud rotary or drive-and-wash drilling methods to depths of 109 to 126 feet below existing grade, respectively. B-2 was re-drilled using drive and wash and NX core to obtain confirmatory rock core.

The proposed boring locations were laid out in the field by a Terracon representative using a scaled site plan provided by Vermont Agency of Transportation (VAOT) and field ties. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT. The locations and elevations of the borings should be considered accurate only to the degree implied by the means and methods used to define them.

Samples of the soil encountered in the borings were obtained using the split-barrel sampling procedures. In the split-barrel sampling procedure, the number of blows required to advance a standard 2-inch O.D. split-barrel sampler the last 12 inches of the typical total 18-inch penetration by means of a 140-pound hammer with a free fall of 30 inches, is the standard penetration resistance value (SPT-N). This value is used to estimate the in-situ relative density of cohesionless soils and consistency of cohesive soils.

The samples were tagged for identification, sealed to reduce moisture loss, and taken to the VAOT laboratory for further examination, testing, and classification. Information provided on the boring logs attached to this report includes soil descriptions, consistency evaluations, boring depths, sampling intervals, and groundwater conditions. The borings were backfilled with cuttings prior to the drill crew leaving the site.

A field log of each boring was prepared by the Terracon field engineer. These logs included visual classifications of the materials encountered during drilling as well as the field engineer's interpretation of the subsurface conditions between samples. Final boring logs included with this report represent the engineer's interpretation of the field logs and include modifications based on laboratory observation and tests of the samples.



STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

**BORING LOG**  
**VT Route 14, Bridge 74 Over Pekin Brook**  
**Calais, Vermont**  
**BHF 037-2(10)**

Boring No.: **B-1**  
Page No.: **1 of 3**  
Pin No.: **s12b144**  
Checked By: **ASP**

Boring Crew: <u>Drilex, JDF</u>	Type: <u>Steel</u>	Casing: <u>SS</u>	Groundwater Observations		
Date Started: <u>3/10/14</u> Date Finished: <u>3/11/14</u>	I.D.: <u>4 in</u>	Sampler: <u>1.38 in</u>	Date	Depth (ft)	Notes
VTSPG NAD83: <u>N 1654568.04 ft E 668328.04 ft</u>	Hammer Wt: <u>300 lb.</u>	Hammer Fall: <u>140 lb.</u>	03/10/14	16.0	While sampling
Station: <u>114.375</u> Offset: <u>26.00LT</u>	Hammer/Rod Type: <u>Auto/N</u>				
Ground Elevation: <u>721.0 ft</u>	Rig: <u>CME 85 Truck</u>	<u>C<sub>E</sub> = 1.33</u>			

Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Blows/6" (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
5		A-1-b, GrSa, dark brown, Rec. = 1.58 ft, (FILL)	11-28-33-22	14.1	28.0	53.3	18.7
		A-1-b, GrSa, brown, Rec. = 0.92 ft, (FILL)	(61)	8.8	30.5	52.6	16.9
		A-2-4, SiSa, gray-brown, Rec. = 0.25 ft, (FILL)	15-18-9-3	23.3	14.4	60.2	25.4
10		A-4, SiSa, dark brown, Rec. = 0.17 ft	2-1-1-2 (2)	29.5	5.0	56.6	38.4
		A-4, GrSiSa, brown/dark brown, Rec. = 0.5 ft	1-1-1-1 (2)	26.7	22.1	40.2	37.7
		A-4, SiSa, brown/dark brown, Rec. = 1.33 ft	3-5-4-4 (9)	25.0	15.5	43.5	41.0
15		A-4, SaSi, gray-brown, Rec. = 1.0 ft	3-4-2-2 (6)	35.3	3.8	47.9	48.3
		A-4, SiSa, gray-brown, Rec. = 0.0 ft	8-8-9-9 (17)	30.8	4.7	11.9	83.4
		A-4, Si, gray, Rec. = 1.17 ft	3-3-3-3 (6)	36.1	0.3	1.6	98.1
20		A-4, Si, gray, Rec. = 1.58 ft	1-1-1-2 (2)	28.5	1.2	5.4	93.4
		A-4, Si, gray, Rec. = 0.83 ft	12-6-2-2 (8)	31.8	1.1	5.6	93.3
		A-4, Si, gray, Rec. = 0.83 ft	3-2-2-3 (4)	29.8		1.7	98.3
25		A-4, Si, gray, Rec. = 1.17 ft	8-7-5-4 (12)				
30		A-4, Si, gray, Rec. = 1.58 ft	4-2-2-2 (4)	34.1		1.0	99.0
35		A-4, Si, gray, Rec. = 1.58 ft	5-4-3-3 (7)	34.6		0.7	99.3
40		A-4, Si, gray, Rec. = 1.67 ft	5-4-2-2 (6)	31.7		0.8	99.2
45		A-4, Si, gray, Rec. = 1.83 ft	3-2-2-4 (4)	39.1		0.6	99.4
		Shelby tube sample, Rec. = 0.0 ft					

Notes:

1. Stratification lines represent approximate boundary between material types. Transition may be gradual.
2. N Values have not been corrected for hammer energy. C<sub>E</sub> is the hammer energy correction factor. C<sub>E</sub> is an estimated value.
3. Water level readings have been made at times and under conditions stated.
4. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.
5. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT.

**Terracon**



STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

**BORING LOG**  
**VT Route 14, Bridge 74 Over Pekin Brook**  
**Calais, Vermont**  
**BHF 037-2(10)**

Boring No.: **B-1**  
Page No.: **2 of 3**  
Pin No.: **s12b144**  
Checked By: **ASP**

Boring Crew: Drilex, JDF  
Date Started: 3/10/14 Date Finished: 3/11/14  
VTSPG NAD83: N 1654568.04 ft E 668328.04 ft  
Station: 114.375 Offset: 26.00LT  
Ground Elevation: 721.0 ft

Casing Steel Sampler SS  
Type: Steel I.D.: 4 in 1.38 in  
Hammer Wt: 300 lb. 140 lb.  
Hammer Fall: 30 in. 30 in.  
Hammer/Rod Type: Auto/N  
Rig: CME 85 Truck C<sub>E</sub> = 1.33

**Groundwater Observations**

Date	Depth (ft)	Notes
03/10/14	16.0	While sampling

Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Blows/6" (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
55		A-4, Si, gray, Rec. = 1.17 ft	4-2-2-2 (4)	34.3		1.0	99.0
		A-4, Si, gray, Rec. = 1.5 ft	4-4-2-3 (6)	30.8		6.1	93.9
60		A-4, Si, gray, Rec. = 1.83 ft	1-1-2-2 (3)	29.9		1.6	98.4
65		A-4, Si, gray, Rec. = 2.0 ft	4-5-5-4 (10)	34.4		1.0	99.0
70		A-4, Si, gray, Rec. = 0.75 ft	3-3-3-4 (6)	34.9		0.2	99.8
75							
80							
85		A-4, Si, gray, Rec. = 1.5 ft	5-6-6-5 (12)	30.9		1.2	98.8
90							
95		A-4, Si, gray, Rec. = 1.58 ft	3-3-3-5 (6)	33.5		3.1	96.9
		A-4, Si, gray, Rec. = 1.75 ft	5-6-6-7	28.1		7.8	92.2

**Notes:**

1. Stratification lines represent approximate boundary between material types. Transition may be gradual.
2. N Values have not been corrected for hammer energy. C<sub>E</sub> is the hammer energy correction factor. C<sub>E</sub> is an estimated value.
3. Water level readings have been made at times and under conditions stated.
4. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.
5. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT.

**Terracon**



STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

BORING LOG

VT Route 14, Bridge 74 Over Pekin Brook  
Calais, Vermont  
BHF 037-2(10)

Boring No.: **B-1**  
Page No.: 3 of 3  
Pin No.: s12b144  
Checked By: ASP

Boring Crew: Drilex, JDF  
Date Started: 3/10/14 Date Finished: 3/11/14  
VTSPG NAD83: N 1654568.04 ft E 668328.04 ft  
Station: 114.375 Offset: 26.00LT  
Ground Elevation: 721.0 ft

Casing: Steel Sampler: SS  
I.D.: 4 in 1.38 in  
Hammer Wt: 300 lb. 140 lb.  
Hammer Fall: 30 in. 30 in.  
Hammer/Rod Type: Auto/N  
Rig: CME 85 Truck  $C_E = 1.33$

Groundwater Observations

Date	Depth (ft)	Notes
03/10/14	16.0	While sampling

Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Blows/6" (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
			(12)				
105		A-4, SaSi, gray, Rec. = 0.83 ft 105.0 ft - 109.0 ft, Weathered bedrock encountered. Difficult drilling from 105' to 109'. Attempted SPT at 109'. SPT refusal encountered at 109'.	14-16-60/2" (76+)	25.0	0.7	31.0	68.3
110		Hole stopped @ 109.0 ft					
115							
120							
125							
130							
135							
140							
145							

Notes:  
1. Stratification lines represent approximate boundary between material types. Transition may be gradual.  
2. N Values have not been corrected for hammer energy.  $C_E$  is the hammer energy correction factor.  $C_E$  is an estimated value.  
3. Water level readings have been made at times and under conditions stated.  
Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.  
4. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT.

Terracon



STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

**BORING LOG**  
**VT Route 14, Bridge 74 Over Pekin Brook**  
**Calais, Vermont**  
**BHF 037-2(10)**

Boring No.: **B-2**  
Page No.: **1 of 3**  
Pin No.: **s12b144**  
Checked By: **ASP**

Boring Crew: Drilex, JDF  
Date Started: 3/17/14 Date Finished: 4/10/14  
VTSPG NAD83: N 1654651.26 ft E 668489.68 ft  
Station: 116.15 Offset: 19.00RT  
Ground Elevation: 720.0 ft

Casing: Steel Sampler: SS  
Type: Steel I.D.: 4 in 1.38 in  
Hammer Wt: 300 lb. 140 lb.  
Hammer Fall: 30 in. 30 in.  
Hammer/Rod Type: Auto/N  
Rig: CME 85 Truck C<sub>E</sub> = 1.33

**Groundwater Observations**

Date	Depth (ft)	Notes
03/17/14	9.0	While sampling

Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Run (Dip deg.)	Core Rec. % (RQD %)	Drill Rate minutes/ft	Blows/6" (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
5		A-2-4, SiSa, Dark brown, Rec. = 0.17 ft, (FILL)				4-2-3-4 (5)	17.3	14.7	52.8	32.5
10		A-4, SaSi Sample stuck in casing. (Casing pulled up and collected sample from casing), brown, Rec. = 0.0 ft				0-0-0-0	25.4	0.7	22.0	77.3
15		Rec. = 0.0 ft				6-5-4-2 (9)				
20		A-4, Si, brown/gray, Rec. = 0.58 ft				2-1-1-1 (2)	36.7	3.1	1.1	95.8
25		Rec. = 0.0 ft				2-2-2-2 (4)				
30		A-4, Si, brown/gray, Rec. = 0.25 ft				3-2-2-3 (4)	35.8	3.6	3.4	93.0
35		A-4, Si, gray, Rec. = 1.42 ft				2-1-2-2 (3)	35.5		3.2	96.8
40		A-4, Si, gray, Rec. = 1.42 ft				2-1-1-2 (2)	26.5	0.2	4.4	95.4
45		A-4, Si, gray, Rec. = 1.5 ft				3-2-2-2 (4)	38.6		1.1	98.9
		A-4, Si, gray, Rec. = 1.0 ft				3-2-2-3	35.7		1.9	98.1

Notes: 1. Stratification lines represent approximate boundary between material types. Transition may be gradual.  
2. N Values have not been corrected for hammer energy. C<sub>E</sub> is the hammer energy correction factor. C<sub>E</sub> is an estimated value.  
3. Water level readings have been made at times and under conditions stated.  
Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.  
4. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT.

**Terracon**



STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

BORING LOG

VT Route 14, Bridge 74 Over Pekin Brook  
Calais, Vermont  
BHF 037-2(10)

Boring No.: **B-2**  
Page No.: **2 of 3**  
Pin No.: **s12b144**  
Checked By: **ASP**

Boring Crew: **Drilex, JDF**  
Date Started: **3/17/14** Date Finished: **4/10/14**  
VTSPG NAD83: **N 1654651.26 ft E 668489.68 ft**  
Station: **116.15** Offset: **19.00RT**  
Ground Elevation: **720.0 ft**

Casing **Steel** Sampler **SS**  
Type: **Steel** I.D.: **4 in** **1.38 in**  
Hammer Wt: **300 lb.** **140 lb.**  
Hammer Fall: **30 in.** **30 in.**  
Hammer/Rod Type: **Auto/N**  
Rig: **CME 85 Truck** **C<sub>E</sub> = 1.33**

Groundwater Observations

Date	Depth (ft)	Notes
03/17/14	9.0	While sampling

Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Run (Dip deg.)	Core Rec. % (RQD %)	Drill Rate minutes/ft	Blows/6" (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
55						(4)				
60		A-4, Si, gray, Rec. = 0.83 ft				3-2-2-2 (4)	33.0		3.4	96.6
65										
70		A-4, Si, gray, Rec. = 0.83 ft				3-3-2-2 (5)	29.9		3.0	97.0
75										
80		A-4, Si, gray, Rec. = 1.08 ft				8-5-5-8 (10)	32.3		2.8	97.2
85										
90		A-4, Si, gray, Rec. = 1.08 ft				8-5-6-10 (11)	31.9	5.0	3.2	91.8
95										

Notes: 1. Stratification lines represent approximate boundary between material types. Transition may be gradual.  
2. N Values have not been corrected for hammer energy. C<sub>E</sub> is the hammer energy correction factor. C<sub>E</sub> is an estimated value.  
3. Water level readings have been made at times and under conditions stated.  
4. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.  
5. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT.

Terracon





STATE OF VERMONT  
AGENCY OF TRANSPORTATION  
MATERIALS & RESEARCH SECTION  
SUBSURFACE INFORMATION

BORING LOG

VT Route 14, Bridge 74 Over Pekin Brook  
Calais, Vermont  
BHF 037-2(10)

Boring No.: **B-2**  
Page No.: 3 of 3  
Pin No.: s12b144  
Checked By: ASP

Boring Crew: Drilex, JDF  
Date Started: 3/17/14 Date Finished: 4/10/14  
VTSPG NAD83: N 1654651.26 ft E 668489.68 ft  
Station: 116.15 Offset: 19.00RT  
Ground Elevation: 720.0 ft

Casing: Steel  
Sampler: SS  
Type: Steel  
I.D.: 4 in  
1.38 in  
Hammer Wt: 300 lb.  
140 lb.  
Hammer Fall: 30 in.  
30 in.  
Hammer/Rod Type: Auto/N  
Rig: CME 85 Truck  
C<sub>E</sub> = 1.33

Groundwater Observations

Date	Depth (ft)	Notes
03/17/14	9.0	While sampling

Depth (ft)	Strata (1)	CLASSIFICATION OF MATERIALS (Description)	Run (Dip deg.)	Core Rec. % (RQD %)	Drill Rate minutes/ft	Blows/6" (N Value)	Moisture Content %	Gravel %	Sand %	Fines %
105		A-4, Si, gray, Rec. = 0.83 ft				6-6-11-13 (17)	29.7	0.7	2.9	96.4
110										
115		SiSa, gray, 115.0 ft - 119.0 ft				14-18-21-30 (39)	22.8	0.1	52.3	47.6
120		Possible gravel from 119 to 121.5 feet indicated by grinding drilling noise								
125		121.5 ft - 126.0 ft, Gray, whitish MUSCOVITE-BIOTITE-QUARTZ PHYLLITE, moderately hard to hard, tight joints (typically fresh to slightly weathered with rust color) dipping from 0° to 55° (typically from 25° to 55° with one horizontal joint).	1	93.5 (79.6)	2.33 1.42 1.42 1.5 0.83					
130		On 4/9/2014, relocated boring 5 feet towards the bridge and redrilled from 115 ft. to 126 ft. using Crawford Drilling Services. Hole stopped @ 126.0 ft								
135										
140										
145										

Notes:

1. Stratification lines represent approximate boundary between material types. Transition may be gradual.
2. N Values have not been corrected for hammer energy. C<sub>E</sub> is the hammer energy correction factor. C<sub>E</sub> is an estimated value.
3. Water level readings have been made at times and under conditions stated.
4. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.
5. Ground surface elevations indicated on the boring logs were estimated based on the grading plan provided by VAOT.

**Terracon**

**APPENDIX B**  
**LABORATORY TEST RESULTS**

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140344      Corrected copy: N/A      Report Date: 3/14/2014 12:57:42  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 44 FT to: 46 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GSH, AL  
Comment: S-17

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):        
75 µm (#200):      99.4%

Hydrometer Analysis  
Particles smaller    % total sample  
0.05 mm:      95.0%  
0.02 mm:      70.5%  
0.005 mm:      18.0%  
0.002 mm:      8.3%  
0.001 mm:      6.9%

Limits  
T-265 Moisture content:      39.1%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index:      NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:      2.757

Gr: 0.0%      D2487: ML

Sa: 0.6%      M145: A-4      Silt

Si: 99.4%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140344

Corrected copy: N/A

Report Date: 3/14/2014 12:57:53

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 44 FT - 46 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140347      Corrected copy: N/A      Report Date: 3/14/2014 1:04:52 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 59 FT to: 61 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GSH, AL  
Comment: S-20

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):      99.8%  
75 µm (#200):      98.4%

Hydrometer Analysis  
Particles smaller    % total sample  
0.05 mm:      89.3%  
0.02 mm:      48.7%  
0.005 mm:      8.2%  
0.002 mm:      3.2%  
0.001 mm:      3.0%

Limits  
T-265 Moisture content:      29.9%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index:      NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:      2.757

Gr: 0.0%    D2487: ML

Sa: 1.6%    M145: A-4      Silt

Si: 98.4%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140347

Corrected copy: N/A

Report Date: 3/14/2014 1:04:55 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 59 FT - 61 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140353      Corrected copy: N/A      Report Date: 3/14/2014 1:11:09 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/11/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 84 FT to: 86 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GSH, AL  
Comment: S-24

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):      99.8%  
75 µm (#200):      98.8%

Hydrometer Analysis  
Particles smaller % total sample  
0.05 mm:      87.4%  
0.02 mm:      49.8%  
0.005 mm:      7.3%  
0.002 mm:      3.3%  
0.001 mm:      3.0%

Limits  
T-265 Moisture content:      30.9%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP

Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:      2.757  
Gr: 0.0%      D2487: ML  
Sa: 1.2%      M145: A-4      Silt  
Si: 98.8%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140353

Corrected copy: N/A

Report Date: 3/14/2014 1:11:14 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 84 FT - 86 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140356      Corrected copy: N/A      Report Date: 3/14/2014 1:19:19 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/11/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 104 FT to: 105 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GSH, AL  
Comment: S-27

Test Results

Sieve Analysis		Limits	
T-88	% Passing		
Total Sample			
75 mm (3.0"):		T-265 Moisture content:	25.0%
37.5 mm (1.5"):		T-89 Liquid Limit:	
19 mm (3/4"):		T-90 Plastic Limit:	
9.5 mm (3/8"):	100.0%	T-90 Plasticity Index:	NP
4.75 mm (#4):	99.8%	Moisture Density	
2.00 mm (#10):	99.3%	Test method:	T-180      Method:
850 µm (#20):	99.1%	Maximum density:	pcf
425 µm (#40):	98.9%	Optimum moisture:	
250 µm (#60):	98.3%	T-100 Specific Gravity:	2.757
150 µm (#100):	92.2%	Gr: 0.7%	D2487: ML
75 µm (#200):	68.3%	Sa: 31.0%	M145: A-4      Sandy Silt
Hydrometer Analysis		Si: 68.3%	
Particles smaller	% total sample		
0.05 mm:	56.4%		
0.02 mm:	28.4%		
0.005 mm:	12.4%		
0.002 mm:	6.1%		
0.001 mm:	4.9%		

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140356

Corrected copy: N/A

Report Date: 3/14/2014 1:19:28 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 104 FT - 105 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140329      Corrected copy: N/A      Report Date: 3/13/2014 11:11:16  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 0 FT to: 2 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-1

Test Results


T-88	Sieve Analysis
	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	95.6%
9.5 mm (3/8"):	89.7%
4.75 mm (#4):	82.0%
2.00 mm (#10):	72.0%
850 µm (#20):	59.2%
425 µm (#40):	46.0%
250 µm (#60):	35.7%
150 µm (#100):	28.0%
75 µm (#200):	18.7%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	14.1%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method:	T-180      Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr:	28.0%    D2487: SM
Sa:	53.3%    M145: A-1-b    Gravelly Sand
Si:	18.7%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140329

Corrected copy: N/A

Report Date: 3/13/2014 11:11:22

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 0 FT - 2 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140331      Corrected copy: N/A      Report Date: 3/13/2014 11:13:10  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 2 FT to: 4 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-2

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	95.4%
9.5 mm (3/8"):	91.8%
4.75 mm (#4):	81.1%
2.00 mm (#10):	69.5%
850 µm (#20):	50.4%
425 µm (#40):	34.7%
250 µm (#60):	26.6%
150 µm (#100):	22.3%
75 µm (#200):	16.9%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits

T-265 Moisture content: 8.8%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index: NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 30.5%    D2487: SM

Sa: 52.6%    M145: A-1-b    Gravelly Sand

Si: 16.9%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140331

Corrected copy: N/A

Report Date: 3/13/2014 11:13:16

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 2 FT - 4 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140330      Corrected copy: N/A      Report Date: 3/13/2014 11:15:00  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 4 FT to: 6 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-3

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):      98.2%  
4.75 mm (#4):      91.7%  
2.00 mm (#10):      85.6%  
850 µm (#20):      74.0%  
425 µm (#40):      59.8%  
250 µm (#60):      47.6%  
150 µm (#100):      38.8%  
75 µm (#200):      25.4%

Hydrometer Analysis  
Particles smaller % total sample  
0.05 mm:  
0.02 mm:  
0.005 mm:  
0.002 mm:  
0.001 mm:

Limits  
T-265 Moisture content: 23.3%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index: NP  
Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr: 14.4%    D2487: SM  
Sa: 60.2%    M145: A-2-4    Silty Sand  
Si: 25.4%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140330

Corrected copy: N/A

Report Date: 3/13/2014 11:15:05

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 4 FT - 6 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140332      Corrected copy: N/A      Report Date: 3/13/2014 11:17:02  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 6 FT to: 8 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-4

Test Results


	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	98.3%
2.00 mm (#10):	95.0%
850 µm (#20):	86.8%
425 µm (#40):	75.7%
250 µm (#60):	66.1%
150 µm (#100):	57.7%
75 µm (#200):	38.4%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

	Limits
T-265 Moisture content:	29.5%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
	Moisture Density
Test method: T-180	Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr: 5.0%	D2487: SM
Sa: 56.6%	M145: A-4      Silty Sand
Si: 38.4%	

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140332

Corrected copy: N/A

Report Date: 3/13/2014 11:17:06

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 6 FT - 8 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140333      Corrected copy: N/A      Report Date: 3/13/2014 11:19:10  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 8 FT to: 10 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-5

Test Results

Sieve Analysis	
T-88	% Passing
Total Sample	
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	87.6%
9.5 mm (3/8"):	86.4%
4.75 mm (#4):	82.5%
2.00 mm (#10):	77.9%
850 µm (#20):	74.2%
425 µm (#40):	68.5%
250 µm (#60):	62.2%
150 µm (#100):	55.1%
75 µm (#200):	37.7%

Hydrometer Analysis	
Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits  
T-265 Moisture content: 26.7%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index: NP

Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr: 22.1%      D2487: SM  
Sa: 40.2%      M145: A-4      Gravelly Silty Sand  
Si: 37.7%

Comments: LAB NOTE: BROKEN ROCK WAS WITHIN SAMPLE.

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140333

Corrected copy: N/A

Report Date: 3/13/2014 11:19:14

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 8 FT - 10 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140334      Corrected copy: N/A      Report Date: 3/13/2014 11:20:45  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 10 FT to: 12 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-6

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	96.0%
4.75 mm (#4):	91.3%
2.00 mm (#10):	84.5%
850 µm (#20):	80.8%
425 µm (#40):	75.7%
250 µm (#60):	70.1%
150 µm (#100):	63.5%
75 µm (#200):	41.0%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	25.0%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method: T-180	Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr: 15.5%	D2487: SM
Sa: 43.5%	M145: A-4      Silty Sand
Si: 41.0%	

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140334

Corrected copy: N/A

Report Date: 3/13/2014 11:20:51

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 10 FT - 12 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140335      Corrected copy: N/A      Report Date: 3/13/2014 11:23:04  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 12 FT to: 14 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-7

Test Results

Sieve Analysis	
T-88	% Passing
Total Sample	
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	99.8%
2.00 mm (#10):	96.2%
850 µm (#20):	88.3%
425 µm (#40):	83.8%
250 µm (#60):	79.9%
150 µm (#100):	72.6%
75 µm (#200):	48.3%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	35.3%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method: T-180	Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr: 3.8%	D2487: SM
Sa: 47.9%	M145: A-4      Sandy Silt
Si: 48.3%	

Comments: LAB NOTE: PIECES OF WOOD WERE WITHIN SAMPLE.

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TZ*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140335

Corrected copy: N/A

Report Date: 3/13/2014 11:23:07

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 12 FT - 14 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140336      Corrected copy: N/A      Report Date: 3/13/2014 11:24:32  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 16 FT to: 18 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-9

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	97.7%
2.00 mm (#10):	95.3%
850 µm (#20):	94.1%
425 µm (#40):	93.3%
250 µm (#60):	92.8%
150 µm (#100):	91.9%
75 µm (#200):	83.4%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits

T-265 Moisture content: 30.8%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index: NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 4.7%    D2487: ML

Sa: 12.0%    M145: A-4    Silt

Si: 83.4%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140336

Corrected copy: N/A

Report Date: 3/13/2014 11:24:37

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 16 FT - 18 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140337      Corrected copy: N/A      Report Date: 3/13/2014 11:26:15  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 18 FT to: 20 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-10

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      99.7%  
850 µm (#20):      99.6%  
425 µm (#40):      99.5%  
250 µm (#60):      99.4%  
150 µm (#100):      99.2%  
75 µm (#200):      98.1%

Hydrometer Analysis  
Particles smaller      % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      36.1%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP  
Moisture Density  
Test method:      T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr:      0.3%      D2487:      ML  
Sa:      1.7%      M145:      A-4      Silt  
Si:      98.1%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140337

Corrected copy: N/A

Report Date: 3/13/2014 11:26:20

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 18 FT - 20 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140338      Corrected copy: N/A      Report Date: 3/13/2014 11:28:39  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 20 FT to: 22 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-11

Test Results

Sieve Analysis	
T-88	% Passing
Total Sample	
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	98.9%
2.00 mm (#10):	98.8%
850 µm (#20):	98.8%
425 µm (#40):	98.8%
250 µm (#60):	98.6%
150 µm (#100):	98.5%
75 µm (#200):	93.4%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits

T-265 Moisture content: 28.5%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index: NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 1.2%    D2487: ML

Sa: 5.3%    M145: A-4    Silt

Si: 93.4%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TZ*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140338

Corrected copy: N/A

Report Date: 3/13/2014 11:28:45

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 20 FT - 22 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140339      Corrected copy: N/A      Report Date: 3/13/2014 11:36:06  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 22 FT to: 24 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-12

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      99.0%  
2.00 mm (#10):      98.9%  
850 µm (#20):      98.9%  
425 µm (#40):      98.9%  
250 µm (#60):      98.8%  
150 µm (#100):      98.7%  
75 µm (#200):      93.3%

Hydrometer Analysis  
Particles smaller      % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      31.8%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP  
Moisture Density  
Test method:      T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr:      1.1%      D2487:      ML  
Sa:      5.6%      M145:      A-4      Silt  
Si:      93.3%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140339

Corrected copy: N/A

Report Date: 3/13/2014 11:36:09

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 22 FT - 24 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140340      Corrected copy: N/A      Report Date: 3/13/2014 11:38:26  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 24 FT to: 26 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-13

Test Results

Sieve Analysis		Limits	
T-88	% Passing		
Total Sample			
75 mm (3.0"):		T-265 Moisture content:	29.8%
37.5 mm (1.5"):		T-89 Liquid Limit:	
19 mm (3/4"):		T-90 Plastic Limit:	
9.5 mm (3/8"):		T-90 Plasticity Index:	NP
4.75 mm (#4):	100.0%	Moisture Density	
2.00 mm (#10):	100.0%	Test method: T-180	Method:
850 µm (#20):		Maximum density:	pcf
425 µm (#40):		Optimum moisture:	
250 µm (#60):		T-100 Specific Gravity:	
150 µm (#100):	99.7%	Gr: 0.0%	D2487: ML
75 µm (#200):	98.3%	Sa: 1.7%	M145: A-4      Silt
		Si: 98.3%	
Hydrometer Analysis			
Particles smaller    % total sample			
0.05 mm:			
0.02 mm:			
0.005 mm:			
0.002 mm:			
0.001 mm:			

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140340

Corrected copy: N/A

Report Date: 3/13/2014 11:38:30

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 24 FT - 26 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140341      Corrected copy: N/A      Report Date: 3/13/2014 11:39:49  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014      Received: 3/11/2014      Tested: 3/11/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 29 FT to: 31 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-14

Test Results


Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):      99.9%  
75 µm (#200):      99.0%

Hydrometer Analysis  
Particles smaller      % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      34.1%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP

Moisture Density  
Test method:      T-180      Method:  
Maximum density:           pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr:      0.0%      D2487:      ML  
Sa:      1.0%      M145:      A-4      Silt  
Si:      99.0%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140341

Corrected copy: N/A

Report Date: 3/13/2014 11:40:05

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 29 FT - 31 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140342      Corrected copy: N/A      Report Date: 3/13/2014 11:47:35  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 34 FT to: 36 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-15

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):        
75 µm (#200):      99.3%

Hydrometer Analysis  
Particles smaller    % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      34.6%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index:      NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 0.0%    D2487: ML  
Sa: 0.7%    M145: A-4    Silt  
Si: 99.3%

Comments: LAB NOTE: A VERY SMALL LAYER OF CLAY WAS NOTICEABLE.

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140342

Corrected copy: N/A

Report Date: 3/13/2014 11:47:50

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 34 FT - 36 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE


Report on Soil Sample

Lab number: E140343      Corrected copy: N/A      Report Date: 3/13/2014 11:49:25  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 39 FT to: 41 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-16

Test Results

Sieve Analysis		Limits	
T-88	% Passing Total Sample		
75 mm (3.0"):		T-265 Moisture content:	31.7%
37.5 mm (1.5"):		T-89 Liquid Limit:	
19 mm (3/4"):		T-90 Plastic Limit:	
9.5 mm (3/8"):		T-90 Plasticity Index:	NP
4.75 mm (#4):	100.0%	Moisture Density	
2.00 mm (#10):	100.0%	Test method:	T-180      Method:
850 µm (#20):		Maximum density:	pcf
425 µm (#40):		Optimum moisture:	
250 µm (#60):		T-100 Specific Gravity:	
150 µm (#100):		Gr: 0.0%	D2487: ML
75 µm (#200):	99.2%	Sa: 0.8%	M145: A-4      Silt
Hydrometer Analysis		Si: 99.2%	
Particles smaller % total sample			
0.05 mm:			
0.02 mm:			
0.005 mm:			
0.002 mm:			
0.001 mm:			

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140343

Corrected copy: N/A

Report Date: 3/13/2014 11:49:28

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 39 FT - 41 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140345      Corrected copy: N/A      Report Date: 3/13/2014 11:50:54  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 51 FT to: 53 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-18

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):      99.9%  
75 µm (#200):      99.0%

Hydrometer Analysis  
Particles smaller    % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      34.3%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP

Moisture Density  
Test method:      T-180      Method:  
Maximum density:           pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr:      0.0%      D2487:      ML  
Sa:      1.0%      M145:      A-4      Silt  
Si:      99.0%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140345

Corrected copy: N/A

Report Date: 3/13/2014 11:50:58

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 51 FT - 53 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140346      Corrected copy: N/A      Report Date: 3/13/2014 11:52:30  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/10/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 54 FT to: 56 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-19

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	100.0%
850 µm (#20):	
425 µm (#40):	
250 µm (#60):	99.9%
150 µm (#100):	99.6%
75 µm (#200):	93.9%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits

T-265 Moisture content: 30.8%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index: NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 0.0%    D2487: ML

Sa: 6.1%    M145: A-4    Silt

Si: 93.9%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TZ*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140346

Corrected copy: N/A

Report Date: 3/13/2014 11:52:33

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 54 FT - 56 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140351      Corrected copy: N/A      Report Date: 3/13/2014 11:55:26  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/11/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 65 FT to: 67 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-21

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):      99.7%  
150 µm (#100):      99.4%  
75 µm (#200):      99.0%

Hydrometer Analysis  
Particles smaller % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content: 34.4%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index: NP

Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr: 0.0%    D2487: ML  
Sa: 1.0%    M145: A-4      Silt  
Si: 99.0%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140351

Corrected copy: N/A

Report Date: 3/13/2014 11:55:30

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 65 FT - 67 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140352      Corrected copy: N/A      Report Date: 3/13/2014 11:56:55  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/11/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 69 FT to: 71 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-22

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):        
250 µm (#60):        
150 µm (#100):      99.9%  
75 µm (#200):      99.8%

Hydrometer Analysis  
Particles smaller % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content: 34.9%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index: NP

Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr: 0.0%    D2487: ML  
Sa: 0.2%    M145: A-4      Silt  
Si: 99.8%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist

*TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140352

Corrected copy: N/A

Report Date: 3/13/2014 11:56:59

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 69 FT - 71 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140354      Corrected copy: N/A      Report Date: 3/13/2014 11:58:30  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/11/2014    Received: 3/11/2014    Tested: 3/11/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-1      Depth: 94 FT to: 96 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-25

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):        
425 µm (#40):      99.9%  
250 µm (#60):      99.4%  
150 µm (#100):      98.5%  
75 µm (#200):      96.9%

Hydrometer Analysis  
Particles smaller % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content: 33.5%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index: NP

Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr: 0.0%    D2487: ML  
Sa: 3.1%    M145: A-4      Silt  
Si: 96.9%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140354

Corrected copy: N/A

Report Date: 3/13/2014 11:58:33

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 94 FT - 96 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140355

Corrected copy: N/A

Report Date: 3/13/2014 11:59:52

Project: CALAIS

Number: BHF 037-2(10)

Site: VT-14 BR-74

Date sampled: 3/11/2014 Received: 3/11/2014 Tested: 3/11/2014 Tested by: J. TOUCHETTE

Station: Offset: Hole: B-1 Depth: 99 FT to: 101 FT

Field description:

Submitted by: TERRACON

Address:

Sample type: SPLIT BARREL

Quantity:

Sample source/Outside agency name:

Location used:

Examined for: MC, GS, AL

Comment: S-26

Test Results

Sieve Analysis	
T-88	% Passing
Total Sample	
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	100.0%
850 µm (#20):	
425 µm (#40):	
250 µm (#60):	99.9%
150 µm (#100):	99.7%
75 µm (#200):	92.2%

Limits	
T-265 Moisture content:	28.1%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP

Moisture Density	
Test method:	T-180
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr:	0.0% D2487: ML
Sa:	7.8% M145: A-4 Silt
Si:	92.2%

Hydrometer Analysis	
Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140355

Corrected copy: N/A

Report Date: 3/13/2014 11:59:55

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-1

Depth: 99 FT - 101 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140379      Corrected copy: N/A      Report Date: 3/24/2014 1:04:16 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14      BR-74  
Date sampled: 3/17/2014      Received: 3/19/2014      Tested: 3/19/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 4 FT to: 6 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-1

Test Results

Sieve Analysis		Limits	
T-88	% Passing		
Total Sample			
75 mm (3.0"):		T-265 Moisture content:	17.3%
37.5 mm (1.5"):		T-89 Liquid Limit:	
19 mm (3/4"):		T-90 Plastic Limit:	
9.5 mm (3/8"):		T-90 Plasticity Index:	NP
4.75 mm (#4):	93.2%	Moisture Density	
2.00 mm (#10):	85.3%	Test method:	T-180      Method:
850 µm (#20):	72.2%	Maximum density:	pcf
425 µm (#40):	59.5%	Optimum moisture:	
250 µm (#60):	50.7%	T-100 Specific Gravity:	
150 µm (#100):	44.1%	Gr: 14.7%	D2487: SM
75 µm (#200):	32.5%	Sa: 52.8%	M145: A-2-4      Silty Sand
		Si: 32.5%	
Hydrometer Analysis			
Particles smaller    % total sample			
0.05 mm:			
0.02 mm:			
0.005 mm:			
0.002 mm:			
0.001 mm:			

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140379

Corrected copy: N/A

Report Date: 3/24/2014 1:04:22 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 4 FT - 6 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140380      Corrected copy: N/A      Report Date: 3/24/2014 1:05:40 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 9 FT to: 11 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-2

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	99.3%
850 µm (#20):	98.9%
425 µm (#40):	98.2%
250 µm (#60):	96.5%
150 µm (#100):	93.1%
75 µm (#200):	77.3%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	25.4%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method:	T-180      Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr:	0.7%    D2487: ML
Sa:	22.1%    M145: A-4    Sandy Silt
Si:	77.3%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140380

Corrected copy: N/A

Report Date: 3/24/2014 1:05:46 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 9 FT - 11 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140381      Corrected copy: N/A      Report Date: 3/24/2014 1:07:49 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 19 FT to: 21 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-4

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	99.4%
4.75 mm (#4):	96.9%
2.00 mm (#10):	96.9%
850 µm (#20):	96.9%
425 µm (#40):	96.7%
250 µm (#60):	96.6%
150 µm (#100):	96.4%
75 µm (#200):	95.8%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	36.7%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method:	T-180      Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr:	3.1%    D2487: ML
Sa:	1.1%    M145: A-4    Silt
Si:	95.8%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140381

Corrected copy: N/A

Report Date: 3/24/2014 1:07:53 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 19 FT - 21 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140382      Corrected copy: N/A      Report Date: 3/24/2014 1:09:22 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 29 FT to: 31 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-6

Test Results

Sieve Analysis	
T-88	% Passing
Total Sample	
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	96.5%
2.00 mm (#10):	96.4%
850 µm (#20):	96.3%
425 µm (#40):	95.8%
250 µm (#60):	95.5%
150 µm (#100):	94.3%
75 µm (#200):	93.0%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits

T-265 Moisture content: 35.8%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index: NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 3.6%    D2487: ML

Sa: 3.4%    M145: A-4    Silt

Si: 93.0%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140382

Corrected copy: N/A

Report Date: 3/24/2014 1:09:25 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 29 FT - 31 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140383      Corrected copy: N/A      Report Date: 3/24/2014 1:11:12 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 34 FT to: 36 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-7

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	100.0%
850 µm (#20):	99.9%
425 µm (#40):	99.6%
250 µm (#60):	99.2%
150 µm (#100):	99.1%
75 µm (#200):	96.8%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	35.5%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method:	T-180      Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr:	0.0%    D2487: ML
Sa:	3.2%    M145: A-4    Silt
Si:	96.8%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140383

Corrected copy: N/A

Report Date: 3/24/2014 1:11:15 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 34 FT - 36 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140384      Corrected copy: N/A      Report Date: 3/24/2014 1:12:46 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 39 FT to: 41 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-8

Test Results

T-88	Sieve Analysis % Passing Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	99.8%
850 µm (#20):	99.6%
425 µm (#40):	99.4%
250 µm (#60):	99.0%
150 µm (#100):	98.0%
75 µm (#200):	95.4%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits	
T-265 Moisture content:	26.5%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
Moisture Density	
Test method: T-180	Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr: 0.2%	D2487: ML
Sa: 4.4%	M145: A-4      Silt
Si: 95.4%	

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140384

Corrected copy: N/A

Report Date: 3/24/2014 1:12:50 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 39 FT - 41 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140385      Corrected copy: N/A      Report Date: 3/24/2014 1:14:19 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 44 FT to: 46 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-9

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	100.0%
850 µm (#20):	
425 µm (#40):	
250 µm (#60):	99.9%
150 µm (#100):	99.6%
75 µm (#200):	98.9%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

	Limits
T-265 Moisture content:	38.6%
T-89 Liquid Limit:	
T-90 Plastic Limit:	
T-90 Plasticity Index:	NP
	Moisture Density
Test method:	T-180      Method:
Maximum density:	pcf
Optimum moisture:	
T-100 Specific Gravity:	
Gr:	0.0%    D2487: ML
Sa:	1.1%    M145: A-4    Silt
Si:	98.9%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140385

Corrected copy: N/A

Report Date: 3/24/2014 1:14:23 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 44 FT - 46 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140386      Corrected copy: N/A      Report Date: 3/24/2014 1:15:48 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 49 FT to: 51 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment: S-10

Test Results


Sieve Analysis  
T-88      % Passing  
Total Sample  
  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):      99.9%  
425 µm (#40):      99.6%  
250 µm (#60):      99.2%  
150 µm (#100):      99.0%  
75 µm (#200):      98.1%

Hydrometer Analysis  
Particles smaller % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
  
T-265 Moisture content: 35.7%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index: NP

Moisture Density  
Test method: T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
  
Gr: 0.0%    D2487: ML  
Sa: 1.9%    M145: A-4      Silt  
Si: 98.1%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140386

Corrected copy: N/A

Report Date: 3/24/2014 1:15:52 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 49 FT - 51 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140387      Corrected copy: N/A      Report Date: 3/24/2014 1:19:05 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014      Received: 3/19/2014      Tested: 3/19/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 59 FT to: 61 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-11

Test Results

	Sieve Analysis
T-88	% Passing
	Total Sample
75 mm (3.0"):	
37.5 mm (1.5"):	
19 mm (3/4"):	
9.5 mm (3/8"):	
4.75 mm (#4):	100.0%
2.00 mm (#10):	100.0%
850 µm (#20):	99.5%
425 µm (#40):	99.3%
250 µm (#60):	99.2%
150 µm (#100):	98.7%
75 µm (#200):	96.6%

Hydrometer Analysis

Particles smaller	% total sample
0.05 mm:	
0.02 mm:	
0.005 mm:	
0.002 mm:	
0.001 mm:	

Limits

T-265 Moisture content: 33.0%

T-89 Liquid Limit:

T-90 Plastic Limit:

T-90 Plasticity Index: NP

Moisture Density

Test method: T-180      Method:

Maximum density:      pcf

Optimum moisture:

T-100 Specific Gravity:

Gr: 0.0%      D2487: ML

Sa: 3.4%      M145: A-4      Silt

Si: 96.6%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140387

Corrected copy: N/A

Report Date: 3/24/2014 1:19:10 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 59 FT - 61 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140388      Corrected copy: N/A      Report Date: 3/24/2014 1:20:20 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014      Received: 3/19/2014      Tested: 3/19/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 69 FT to: 71 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-12

Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):      99.8%  
425 µm (#40):      99.3%  
250 µm (#60):      98.8%  
150 µm (#100):      98.6%  
75 µm (#200):      97.0%

Hydrometer Analysis  
Particles smaller      % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      29.9%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP

Moisture Density  
Test method:      T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr:      0.0%      D2487:      ML  
Sa:      3.0%      M145:      A-4      Silt  
Si:      97.0%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140388

Corrected copy: N/A

Report Date: 3/24/2014 1:20:25 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 69 FT - 71 FT

T-88 Particle size analysis





Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140389      Corrected copy: N/A      Report Date: 3/26/2014 11:26:47  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 79 FT to: 81 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GSH, AL  
Comment: S-13


Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      100.0%  
850 µm (#20):      100.0%  
425 µm (#40):      99.6%  
250 µm (#60):      99.4%  
150 µm (#100):      99.2%  
75 µm (#200):      97.2%

Hydrometer Analysis  
Particles smaller    % total sample  
0.05 mm:      87.9%  
0.02 mm:      41.4%  
0.005 mm:      5.2%  
0.002 mm:      1.3%  
0.001 mm:      1.0%

Limits  
T-265 Moisture content:      32.3%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP  
Moisture Density  
Test method:    T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:      2.757  
Gr:    0.0%    D2487: ML  
Sa:    2.8%    M145: A-4    Silt  
Si:    97.2%

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140389

Corrected copy: N/A

Report Date: 3/26/2014 11:26:52

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 79 FT - 81 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140390      Corrected copy: N/A      Report Date: 3/24/2014 1:23:53 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014      Received: 3/19/2014      Tested: 3/19/2014      Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 89 FT to: 91 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-14


Test Results

Sieve Analysis  
T-88      % Passing  
Total Sample  
75 mm (3.0"):        
37.5 mm (1.5"):        
19 mm (3/4"):        
9.5 mm (3/8"):        
4.75 mm (#4):      100.0%  
2.00 mm (#10):      95.0%  
850 µm (#20):      93.0%  
425 µm (#40):      92.8%  
250 µm (#60):      92.6%  
150 µm (#100):      92.5%  
75 µm (#200):      91.8%

Hydrometer Analysis  
Particles smaller      % total sample  
0.05 mm:        
0.02 mm:        
0.005 mm:        
0.002 mm:        
0.001 mm:     

Limits  
T-265 Moisture content:      31.9%  
T-89 Liquid Limit:  
T-90 Plastic Limit:  
T-90 Plasticity Index:      NP  
Moisture Density  
Test method:      T-180      Method:  
Maximum density:      pcf  
Optimum moisture:  
T-100 Specific Gravity:  
Gr:      5.0%      D2487:      ML  
Sa:      3.2%      M145:      A-4      Silt  
Si:      91.8%

Comments: LAB NOTE: SOME SMALL STONES WERE WITHIN SAMPLE.

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140390

Corrected copy: N/A

Report Date: 3/24/2014 1:23:57 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 89 FT - 91 FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE


Report on Soil Sample

Lab number: E140391      Corrected copy: N/A      Report Date: 3/24/2014 1:25:32 P  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 3/17/2014    Received: 3/19/2014    Tested: 3/19/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2      Depth: 105 FT to: 107 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: SPLIT BARREL      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS, AL  
Comment: S-15

Test Results

Sieve Analysis		Limits	
T-88	% Passing		
Total Sample			
75 mm (3.0"):		T-265 Moisture content:	29.7%
37.5 mm (1.5"):		T-89 Liquid Limit:	
19 mm (3/4"):		T-90 Plastic Limit:	
9.5 mm (3/8"):		T-90 Plasticity Index:	NP
4.75 mm (#4):	99.4%	Moisture Density	
2.00 mm (#10):	99.3%	Test method:	T-180      Method:
850 µm (#20):	99.1%	Maximum density:	pcf
425 µm (#40):	98.9%	Optimum moisture:	
250 µm (#60):	98.8%	T-100 Specific Gravity:	
150 µm (#100):	98.6%	Gr: 0.7%	D2487: ML
75 µm (#200):	96.4%	Sa: 2.9%	M145: A-4      Silt
		Si: 96.4%	
Hydrometer Analysis			
Particles smaller % total sample			
0.05 mm:			
0.02 mm:			
0.005 mm:			
0.002 mm:			
0.001 mm:			

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist 

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140391

Corrected copy: N/A

Report Date: 3/24/2014 1:25:37 P

Project: CALAIS


Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2

Depth: 105 FT - 107FT

T-88 Particle size analysis



Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list  
TERRACON  
T. ELIASSEN  
J. TOUCHETTE

Report on Soil Sample

Lab number: E140619      Corrected copy: N/A      Report Date: 4/11/2014 8:50:06 A  
Project: CALAIS      Number: BHF 037-2(10)      Site: VT-14 BR-74  
Date sampled: 4/9/2014    Received: 4/10/2014    Tested: 4/10/2014    Tested by: J. TOUCHETTE  
Station:      Offset:      Hole: B-2A      Depth: 117 FT to: 119 FT  
Field description:  
Submitted by: TERRACON      Address:  
Sample type: CASING      Quantity:  
Sample source/Outside agency name:  
Location used:      Examined for: MC, GS  
Comment:

Test Results

Sieve Analysis		Limits	
T-88	% Passing		
Total Sample			
75 mm (3.0"):		T-265 Moisture content:	22.8%
37.5 mm (1.5"):		T-89 Liquid Limit:	
19 mm (3/4"):		T-90 Plastic Limit:	
9.5 mm (3/8"):		T-90 Plasticity Index:	NP
4.75 mm (#4):	100.0%	Moisture Density	
2.00 mm (#10):	99.9%	Test method:	T-180      Method:
850 µm (#20):	99.8%	Maximum density:	pcf
425 µm (#40):	99.6%	Optimum moisture:	
250 µm (#60):	94.8%	T-100 Specific Gravity:	
150 µm (#100):	76.8%	Gr: 0.1%	D2487: SM
75 µm (#200):	47.9%	Sa: 52.0%	M145: A-4      Silty Sand
		Si: 47.9%	
Hydrometer Analysis			
Particles smaller % total sample			
0.05 mm:			
0.02 mm:			
0.005 mm:			
0.002 mm:			
0.001 mm:			

Comments:

Reviewed by: T. Eliassen, P.G., Transportation Geologist *TE*

Vermont Agency of Transportation  
Materials and Research Section  
1 National Life Drive  
Montpelier, VT 05633-5001

Distribution list

Report on Soil Sample

Lab number: E140619

Corrected copy: N/A

Report Date: 4/11/2014 8:50:15 A

Project: CALAIS

Number: BHF 037-2(10)

Site: VT-14 BR-74

Hole: B-2A

Depth: 117FT - 119FT

T-88 Particle size analysis

